



1. ALL EDGES TO BE NEATLY SAWCUT & ITEM 407, TACK COAT, AC-20, APPLIED TO EXPOSED SURFACES PRIOR TO PLACEMENT OF NEW PAVEMENT.
2. BUTT JOINTS SHALL BE CREATED AT ALL ASPHALT & CONCRETE DRIVES. LENGTH OF BUTT JOINT AT THESE AREAS SHALL BE 1'±.
3. CONTRACTOR SHALL SAND AND SEAL ALL JOINTS BETWEEN THE EXISTING PAVEMENT AND NEW PAVEMENT PLACEMENT. ALL PAVEMENT OVERLAY AREAS SHALL HAVE BUTT JOINTS CONSTRUCTED PER DETAIL. COST OF THESE ITEMS SHALL BE INCLUDED IN VARIOUS RELATED BID ITEMS.

Pomeroy & Associates Ltd.

Consulting Engineers & Surveyors
 2550 Corporate Exchange Drive ~ Suite 10
 Columbus, Ohio 43231
 Phone (614)885-2498 • Fax (614)885-2886

**DETAIL
 BUTT JOINT
 VILLAGE OF ASHVILLE
 ASHVILLE, OHIO**

JOB NO.	2420
DRAWN BY	IJJ
CHECKED BY	CMT
DATE	04/24/2017