FY20 – PAVEMENT SCOPE OF SERVICES

PROJECT NAME:	PIC-SR 316/752-13.05/0.000	PID: 107824
County:	Route:	SECTION:
PIC	316	13.05-13.68

1. PROJECT IDENTIFICATION:

PIC-SR 316 – 13.05-13.68 Functional Class: 05 – Major Collector (Rural)

2. PURPOSE AND NEED:

PIC-316-13.05-13.33 was last maintained in 2010 by PID 83638. This route is currently displaying deteriorations including raveling (LO), rutting (LO), transverse cracks (MF), edge cracking (MF) and crack seal deficiencies (O). Resurfacing and repairs are needed on this route to ensure pavement integrity and to provide the traveling public with safe driving surfaces.

PIC-316-13.05-13.33 2017 PCR: 79 2017 Structural Defect: 12.0 Note: This section of pavement is composite pavement.

PIC-316-13.33-13.68 was last maintained in 2010 by PID 83638. This route is currently displaying deteriorations including raveling (LO), crack seal deficiencies (E), rutting (LO), traverse cracks & an unjointed base (MF), wheel track cracks (LO), block and transverse cracking (LO), longitudinal joint cracks (flexible pavement widening crack) (MF), thermal cracks (MO). Resurfacing and repairs are needed on this route to ensure pavement integrity and to provide the traveling public with safe driving surfaces.

PIC-316-13.33-13.68 2017 PCR: 81 2017 Structural Defect: 7.3 Note: This section of pavement is flexible pavement.

3. PROJECT INITIATION PACKAGE: Yes \boxtimes No \square

Site visit conducted 5/22/18 with Dave Rankin, Scott Rice, Tim Peddicord, Bob Mcneill, Grace Wesner, Frank Christman and Chris Tebbe.

All noted red flags from field visits contained within scope.

4. PROJECT LIMITS:

From: PIC-316-13.05 (*Jefferson Avenue*) To: PIC-316-13.68 (*Station Street*) Project Length: 0.63 centerline miles Work Length: 0.63 centerline miles

The following sections are inside a Village: *The Village of Ashville*:

- PIC-316-13.05 to 13.68

5. GENERAL DESCRIPTION OF WORK:

 1325 yd² Item 251-Partial Depth Pavement Repair (Asphalt Concrete Base), As Per Plan: Repair areas shall be determined by the project engineer before the beginning of work. Repairs shall consist of removing 3" of pavement and placing 3" of Item 301 – Asphalt Concrete Base, PG64-22. Work shall be performed prior to resurfacing and repair areas are to be included into general resurfacing. To Be Determined with Pavement Engineer/County Manager during detailed field review.

Designer Note:

- Final locations and quantities need to be requested by the designer at least 1 month prior to Stage 3 file date.
- Item 251-Partial Depth Pavement Repair (Asphalt Concrete Base), As Per Plan: Repair areas shall be determined by the project engineer before the beginning of work. Repairs shall consist of removing 5" of pavement and placing 5" of Item 301 – Asphalt Concrete Base, PG64-22. Work shall be performed prior to resurfacing and repair areas are to be included into general resurfacing. To Be Determined with Pavement Engineer/County Manager during detailed field review.

Designer Note:

- Final locations and quantities need to be requested by the designer at least 1 month prior to Stage 3 file date.
- TBD yd² Item 253- Pavement Repair, As Per Plan: Repair areas shall be determined by the project engineer before the beginning of work. Repairs shall consist of removing X"-X" of pavement and placing X" of Asphalt on X" of Item 304. Work shall be performed prior to resurfacing. To Be Determined with Pavement Engineer/Village during detailed field review.

Designer Note:

- This repair type is to be used on SR-316
 - These repairs are intended to be adjacent to the curb and gutter replacement
 - Started with 2' wide repairs, but in agreement with the Village, a wider repair may be more beneficial

General Work to be performed on PIC-316:

- 1.5" Item 254 Pavement Planning, Asphalt Concrete (check with Village if they want milled material)
 1.5" Item 441 Asphalt Concrete Surface Course, Type 1, PG64-22
- Item 407 Non-Tracking Tack Coat
- *Potential for variable depth milling to reduce the centerline pavement thickness and flatten the cross slope in order to maximize curb reveal/preserve the curb

Notes:

(1). Butt joints begin/end of project, at milling limits, and bridges not being paved over. Not intended to include butt joints at paved driveways.

(2). Item 623 – Monument Box Adjusted to Grade - 4 each

(3) Item 611 - Manhole Adjusted to Grade - 4 each

(4). Item 638 - Valve Box Adjusted to Grade - 4 each

(5). Curb and gutter replacement on SR-316 within the Village of Ashville - locations where necessary

- The Village intends to raise the curb and gutter (and sidewalk) in areas where this is possible. Curb and gutter will be replaced (along with full depth pavement repairs along the curb line) where the curb and sidewalk cannot be raised. Locations and quantities will be determined once survey has been completed and additional pavement coring.

The survey work is being completed and we expect to have the topographic survey by mid-October. We expect the curb and gutter to be replaced in the areas that we show on the preliminary plan that we sent on September 19th. We conducted several extensive site visits to determine the fall from the right-of-way and road surface drainage to determine the limits of the work in the various areas. I have confidence that the design based on the survey will be within 5% of what we estimated.

Based on our preliminary design we are looking at the following edge milling, curb and gutter quantities for the work on PIC-316:

Item 202 – Curb Removed – 5150 LF	Item 609 – Straight 18" Concrete Curb with 4"
Item 202 – Walk Removed – 25516 SF	Underdrain – 4853 LF
Item 608 – Concrete Walk – 24616 SF	Item 253 – Pavement Repair, As Per Plan – 2805 SY [Assumes 4'
Item 609 – Curb Ramps – 38 EA	wide edge milling at variable depths of 0° to 4°]

(6). Existing Plans, Copy of Destape, and SLD's have been placed in following location in project folder: I:\ProjectData\107824_PIC-316-13.05\ProjAdmin\Planning\Scopes\Existing Info

6. PRIOR STUDIES/PLAN (IDENTIFY):

2010 PID 83 1999 PID 17				Grade Polymer Concrete, Type B mediate, 1.25" Item 448 Surface
7. DESIGN SPEED		35 mph (25 mp		,
8. ALIGNMENT:	New 🗌	Existing \boxtimes	Combination \Box	Journalized Alignment \Box
9. PROFILE:	New 🗆	Combination \Box	Salvage ⊠	
10. SCHEMATIC PI	LAN: Yes 🖂	No \Box		
11. TYPICAL SECT	ION: Yes 🖂	No \Box		

12. TRAFFIC DATA:

	CURRENT TRAFFIC (PIC 2016)		OPENING DAY (2020)		DESIGN YEAR (2032)	
	ADT	ADTT	ADT	ADTT	ADT	ADTT
PIC-316-13.05-	4339	93.24	4700	94	4800	96

13. Crash Analysis: Yes ⊠ No □ Possible □ (To Be Determined) This project does require a crash analysis for SR-316. An email requesting the crash analysis was sent on 5/29/18 to the D6 Safety Team, and a response was requested by 6/12/18. Any recommendations based on the results of the crash analysis have been added to the scope. A copy of the crash analysis has been placed within the project planning folder.

14. TYPE OF ACC	ESS: Limited \Box	Controlled \Box	Non-Controlled \boxtimes
15. FENCING:	Yes \Box	No 🖂	
16. LIGHTING:	Yes \Box	No 🖂	
17. SIGNING:	Yes 🖂	No 🗆	
SP 316	Villago of Ashvillo		

- SR-316 Village of Ashville:
 - $\circ \quad \mbox{Scioto Street: 2 no pedestrian crossing signs needed}$
 - Cromley Street: 2 pedestrian crossing signs needed
 - Need a permanent stop sign here, as well.

The Village will change the preliminary design to reflect the installation of permanent Signage at all necessary locations.

- Main/Long Street: 2 no pedestrian crossing signs needed
- Wright Street: 2 pedestrian crossing signs needed

18. GUARDRAIL:

No \Box Possible \Box (To Be Determined)

19. SIGNALS:

Yes \boxtimes No \square Possible \square (To Be Determined)

- The Village of Ashville requests that ODOT determine if the three signals along SR-316 are warranted
 - \circ The following intersections are the signals that need a warrant analysis:
 - Station Street and SR-316
 - SR-316 at Main and Long Streets

Yes 🖂

- Scioto Street and SR-316
- After performing signal warrants, none of the above signals are warranted to stay in place
 - The Village of Ashville is to advise how to move forward at these signalized intersections

The Village is going to look at specific ways to address the removal of the signalized intersections. I reviewed the signal warrant information provided on 9-25-18 and the signals at the above-referenced intersections do not meet any of the various warrants.

If these are to go to 4-way stops: Who pays for the removal of the signals and erection of proper permanent signage? Is there a desired timeline for removal of the signals from ODOT?

The intersection at Madison\Plum and SR 316 (Long Street) has a significant number of pedestrians during school hours and should be considered part of a Safe Route to Schools. We will include in our project estimate the installation of a Rectangular Rapid Flashing Beacons (RRFB) system at this intersection.

• The Village wishes to incorporate safe crosswalk upgrades if the signals are not warranted

*Signal warrant request sent on 5/24/18

20. PAVEMENT MARKING: Yes \boxtimes No \square

PIC-316/752

Item 644 – Thermoplastic Pavement Marking

Item 646 – Epoxy Pavement Marking (for all concrete bridge decks)

The epoxy needs to be alternate bid for Polycarb Mark 55.4.

All center lines shall be 4". All edge lines and lane lines shall be 6".

Standard crosswalk striping should be included along SR-316 and SR-752:

- There is one spot that has existing ladder crosswalk striping across SR-752
 - This is a flashing crosswalk to get to and from Teays Valley High School
 - Stripe back with ladder striping

Include school markings and RR striping with this project.

Replace stop bars where they are affected by the paving operation

- Only replace if they were in place beforehand

21. DELINEATION:

Barrier Reflectors:	Yes 🖂	No 🗆
Delineators:	Yes \Box	No 🖂
Raised Pavement Markers:	Yes 🖂	No 🗌

There are no special RPMS needed for PIC-316-13.05-13.68.

There are special RPMs needed for PIC-752-0.00-8.43. Follow the link below to see the specifications:

22. ROADSIDE DEVELOPMENT:	Yes 🗆	No 🖂
23. REST AREAS:	Yes 🗆	No 🖂
24. DRAINAGE/CULVERTS:	Yes 🖂	No \Box Possible \Box (To Be Determined)

a. Perform a 3" mill/fill pavement repair at all culverts that have been capped with concrete.

- b. Aggregate drains need to be installed in all full depth repair locations.
- c. Drainage work to be included within the Village of Ashville

i. Catch basins, conduit, etc. – a more detailed survey will be performed by the Village

The survey work is being completed and we expect to have the topographic survey by mid-October. We expect the storm sewer work to be close to what is shown on the preliminary plan that we sent on September 19th. We conducted several extensive site visits to determine the existing drainage system and drainage patterns to determine the limits of the work in the various areas. I have confidence that the design based on the survey will be within 5% of what we estimated.

ad on our proliminary design we are looking at the following drainage quantities for the work on PIC 316

Based on our preliminary design we are looking at the following drainage quantities for the work on PIC-316:					
Item 202 – Manhole Removed – 6 EA			Item 604 – Manhole – 16 EA		
Item 202 – Catch Basin or Inlet Remo	oved – 30 EA		Item 611 –	12" Conduit, Type B – 977 FT	
Item 604 – Catch Basin – 20 EA			Item 611 –	15" Conduit, Type B – 556 FT	
Item 604 – Curb & Gutter Inlet – 3	33 EA		Item 611 –	18" Conduit, Type B – 455 FT	
Item 604 – Manhole Adjusted to G	Grade – 5 EA				
25. INTERCHANGES:	Yes 🗆	No 🖂			
26. BRIDGES (Tim Peddicord):	Yes 🗵			o Be Determined)	
If applicable see attached Bridge Scope of Work No Bridge work on StRt-316					
27. INVESTIGATE PREFABRICATED STRUCTURE:			Yes 🗆	No 🖂	
28. SUBSURFACE INVESTIGATIO	N:		Yes 🗆	No 🖂	
29. BIKEWAYS:			Yes 🗆	No 🖂	
30. MASS TRANSPORTATION:			Yes 🗆	No 🖂	
31. RAILROADS:			Yes 🖂	No 🗆	

Designer to coordinate with Norfolk Southern Railroad for crossing at PIC-316 SLM 13.29 and PIC-752 SLM 1.58. Agreement will be required. Initial coordination should begin immediately and be sent out with "Begin In-House Design" submittal.

Designer Note:

There is an abandoned RR that crosses PIC-316 at 13.24 and PIC-752 at 1.58. Please, still provide plan sheets at these locations to coordinate with CO about whether or not RR coordination is needed at abandoned RR tracks.

32. SERVICE ROADS:

33. SIDE ROADS:

Pavement at all approaches should extend back to the right of way limits, with a minimum distance of 20' beyond the edgeline with the following exceptions:

-SR-316:

West Station Street – this roadway will be paved prior to the resurfacing project 0

No 🗌

Yes 🖂

Yes \Box No 🖂

34. RETAINING WALLS:	Yes 🗆	No 🖂		
35. NOISE WALL:	Yes 🗆	No 🖂		
36. AERIAL PHOTOGRAPHY AND/OR MAPPIN	G: Yes \square	No 🖂		
 37. FIELD SURVEYS: Yes ⊠ No □ Possible □ (To Be Determined) No internal field survey is needed. The Village of Ashville plans to perform additional survey work along SR-316. 				
38. MAINTENANCE OF TRAFFIC: No lane closure hour restrictions. Lane Closure coordination with MOT Engineer.	Yes \boxtimes es anticipated to be s	No □ ingle lane via flaggers. Final		
LEO hours need included at all signalized inter-	sections.			
39. MAINTENANCE OF PEDESTRIAN TRAFFIC: Yes \Box No \Box Possible \Box (To Be Determined) Yes, pedestrian accommodations within work zones should be provided if some sidewalks are to be closed for reconstruction.				
40. MAINTENANCE OF RAILROAD TRAFFIC: Yes ⊠ No □ Designer to coordinate with Norfolk Southern for crossings at PIC-316 SLM 13.290 and PIC-752-1.58. Agreement will be required. Initial coordination should begin immediately and be sent out with "Begin In-House Design" submittal.				
41. ADDITIONAL SAFETY IMPROVEMENTS:	Yes 🗆 No 🛛 Po	ssible \Box (To Be Determined)		
42. R/W ACQUISITION ANTICIPATED: Yes \Box No \boxtimes				
43. R/W ENCROACHMENT: Yes ⊠ On the SR-752 Project not the SR-316 Project	No 🗆 Po	ossible \Box (To Be Determined)		

44. UTILITY IMPACTS ANTICIPATED: Yes \Box No \Box Possible \boxtimes (To Be Determined)

A more detailed survey is being conduction by the Village of Ashville along SR-316. Once the survey has been completed, it will be easier to determine whether or not utilities will be impacted.

The survey work is being completed and we expect to have the topographic survey by mid-October. We do not expect conflicts with private utilities based on the work planned but we will notify ODOT of any potential conflicts. We are keeping all the work within existing right-of-way, so we will coordinate any relocation work, if necessary.

Designer Note – Please add the following plan note – **UTILITIES**:

THE ODOT CONTRACTOR IS REQUIRED TO CONTACT OUPS A MINIMUM OF 48 HOURS EXCLUDING WEEKENDS AND HOLIDAYS TO PERMIT ALL UNDERGROUND UTILITIES AN OPPORTUNITY TO MARK THEIR LINES. IT IS ALSO THE ODOT CONTRACTOR'S RESPONSIBILITY TO CONTACT ALL NON-MEMBERS OF OUPS DIRECTLY A MINIMUM OF 48 HOURS' NOTICE EXCLUDING WEEKENDS AND HOLIDAYS TO PROVIDE THEM WITH THE SAME OPPORTUNITY.

IT IS ODOT'S EXPECTATION THAT ALL GUARD RAIL POSTS WILL BE INSTALLED IN THE SAME LOCATIONS AND THERE WILL BE NO DISRUPTION TO UNDERGROUND UTILITIES. IF THERE IS A UTILITY MARKING WITHIN THE TOLERANCE ZONE OF A UTILITY LOCATE FROM THE PROPOSED GUARDRAIL PLACEMENT IT IS THE ODOT CONTRACTORS RESPONSIBILITY TO DIRECTLY CONTACT THE IMPACTED UTILITY AND WORK WITH THEM TO FIND A SOLUTION THAT DOES NOT CHANGE THE GUARDRAIL PLACEMENT OR DAMAGE THE EXISTING UTILITY. NO UTILITY RELOCATION WILL BE REIMBURSED NOR WILL DELAY CLAIMS BE PERMISSIBLE BASED ON LACK OF COORDINATION BETWEEN THE ODOT CONTRACTOR AND THE IMPACTED UTILITY.

45. ENVIRONMENTAL DOCUMENT TYPE ANTICIPATED:

- \boxtimes C1 C2
- D1
- D2
- \square D3

0

Other Higher Level Document \Box

46. PROJECT LIMITS WITHIN FLOODPLAIN: Yes 🗆 No 🖂

Due to the Environmental Document being a Level C1 - it does not matter if the project is located within a floodplain. If the environmental document level changes, then existing floodplains will need to be researched.

47. ENVIRONMENTAL ISSUES ANTICIPATED:

48.	COMPLETE S'	TREETS	CONSIDERATION:	

ADA Curb Ramps required at crosswalk locations within Village Limits.

- There are ~34 curb ramps that need upgraded along SR-316 with this project
 - Jefferson Avenue: 4 curb ramps
 - 1 spot with a steep grade may need to redo sidewalk at this corner
 - Scioto Street: 2 landing pads and curb ramps 0
 - Cromley Street: potential spot for CDBG intersection upgrade
 - 2 ramps needed on the North side of the intersection
 - 2 new ramps and crosswalk (across SR-316) because the sidewalk ends on the South side of the intersection
 - RR Tracks: 2 curb ramps needed on the North side (no sidewalk on the South side) 0
 - Main and Long Street: replace all 4 curb ramps 0
 - Wright Street: Replace all 4 curb ramps 0
 - Church Street: Replace 2 curb ramps 0
 - Madison/Plum Street: 0
 - The Village has requested potentially placing RRFB crosswalks in two locations at this intersection because there is low visibility
 - Replace 4 curb ramps
 - Cherry Street: Replace 2 curb ramps
 - Harrison Street: Replace 2 ramps
 - Station Street: West side of the intersection is getting upgraded with CDBG funding 0
 - 2 curb ramps needed on the East side of the intersection

*Installation of RRFBs cannot be funded by Central Office safety money. A rough estimate for the Village to install RRFBs in the 3 locations where the signals are not warranted is \$30,000. The Village of Ashville is to advise whether or not they wish to add them to the project.

The intersection at Madison\Plum and SR 316 (Long Street) has a significant number of pedestrians during school hours and should be considered part of a Safe Route to Schools. We will include in our project estimate the installation of a Rectangular Rapid Flashing Beacons (RRFB) system at this intersection.

We do not anticipate the need for RRFB's at the other intersections, as long as they are controlled with stop signs.

49. NHS ROUTE:

Yes	No	\boxtimes
100	110	<u> </u>

Page 7 of 8

No 🗌

Yes \boxtimes

	Allac			
50. FEDERAL TRUCK ROUTE (FAP):	Yes 🗆	No 🖂		
51. DRIVEWAYS:	Yes 🖂	No 🗆		
This project shall include items for the paving of drive aprons. Work for all drive aprons shall include paving the existing conditions. If the apron is asphalt then pave it with mainline pavement. If the apron is aggregate then use Item 617. (Typically - 5'(ex. Asphalt), 5'(ex. aggregate), 2' (ex. concrete). - On SR-316: the Village of Ashville wishes to have driveway aprons paved with concrete.				
The Village standards require the installation of concrete alley and driveways within the right of way. So it is our intent to replace drive approaches as necessary and as shown on the preliminary design plans.				
Based on our preliminary design we are looking at the following alley and driveway approach quantities for the work on PIC-316: Item 452 – 6" Non-Reinforced Concrete Pavement, Class C – 382 SY [Driveways – COC 2201] Item 452 – Non-Reinforced Concrete Pavement, Class C – 183 SY [Alleys – COC 2150, Type II]				
52. MAILBOX APPROACHES:	Yes 🗵	No 🗆		
This project shall include items for the paving of mailbox pulle existing conditions – if it is asphalt pave it, if it is aggregate –		l mailboxes shall pave to		
53. ITS (Nick Hegemier):	Yes 🗆	No 🖂		
54. RWIS Sensor:	Yes 🗆	No 🖂		
55. ATR:	Yes 🗆	No 🖂		
56. LEGISLATION:	Yes 🖂	No 🗆		
This project goes through the Village of Ashville. See S		8		

This project will require funding from the Village of Ashville for drainage upgrades, along with pavement repairs along SR-316..

57. OTHER WORK NOT DESCRIBED ABOVE: Yes \boxtimes No \square Possible \square (To Be Determined)

- This will be a Part 1/Part 2 project _
 - The Village of Ashville will complete the design for SR-316 because of the heftier design 0 efforts such as the curb and gutter replacement, any drainage work and the full depth pavement repair locations, along with the resurfacing on SR-316

58. DELIVERABLES REQUIRED (but not limited to):

- Prelim Coordination Plan (Env and R/R)
- Stage 3 Plan for Review •
- Final Plan Package

All Project Development to follow the current version of the ODOT Plan Development Process and applicable Design Manuals.

No Bridge Involvement on StRt-316 Pave over using the same treatment as roadway -

GUARDRAIL SCOPE OF WORK

PIC-316

No guardrail work needed on PIC-316 between SLM 13.05 – 13.68.