Village of Ashville Exhibit B

Village of Ashville Quarter Mile Track Resurfacing



Fax: 740-983-9650 www.roesebros.com

Village of Ashville Attn: Franklin Christman 300 E. Station St. Ashville, Ohio 43103 740.983.6367 fchristman@ashvilleohio.gov

RE: Village of Ashville - Park Improvements

Scope of Work:

- Total Area approximately 1,854 sy.
- Mill existing asphalt materials hauling them offsite.
- Place 1" ODOT #304 limestone for leveling and drainage purposes.
- Place 1.5" ODOT #448 Type II Intermediate asphalt and 1.5" ODOT #448 Type I surface asphalt.
- Final compaction.

		Unit	Unit		
	Unit	Price	Price	Material/Labor	
	Size				
Material	(cy)	Labor	Material	Total	Total Price
Excavation	103	68.00	30.00	98.00	10,094.00
ODOT #304 Limestone	51	100.00	46.00	146.00	7,446.00
ODOT #448 Type II Intermediate Asphalt	80	56.00	130.00	186.00	14,880.00
ODOT #448 Type I Surface Asphalt	80	58.00	150.00	208.00	16,640.00
Total Price					\$49,060.00

Terms and Conditions:

- All materials for this project are tax-exempt.
- Prevailing Wage rates do not apply for this project.
- All materials are guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices.
- This proposal is valid for 30 days.
- Payment Terms Net 30 days.

Respectfully Submitted By:	Date:
Bruce L. Roese	
The above Proposal, Terms and Conditions, is hereby Accepted:	
Bv:	Date:
Franklin Christman, Village Administrator	

January 16, 2021